

TRANSPORT

INFORMATION

DOCUMENT

Revision: 11th February 2013

Page 1 of 11



Introduction


This document is organised to assist the customers who arrange their own transport of Dincel Construction System. Dincel Construction System currently has no transportation facility outside of the Sydney City Metropolitan area.

Customers who require a transportation company may contact Dincel Construction System for the recommended transportation company list.

Description of Packaging for Transportation by Truck

The 200P-1 panels are packed with timber frames in packs of ten and twelve. The timber frames are nailed together and then bound by plastic strapping. When loaded on a truck, the 200P-1 packs are placed with a ten and twelve pack side by side to utilise the maximum amount of space on the deck of the trailer. Packs containing lengths less than 2800mm have frames spaced 1600mm apart, whereas packs containing lengths longer than 2800mm have frames spaced 2280mm apart. This is to provide maximum support and stability for the panels whilst being loaded and transported.

The dimensions of the 200P-1 packs can be seen below:







110P-1 panels are all packed into packs of twenty in timber frames; nailed together and then bound by plastic strapping. As such, any two 110P-1 packs can be loaded side by side to fill the width of the truck's deck. The spacing between the two timber frames on each pack is determined by the panel length in the same way as the 200P-1 panels.

The dimensions of the 110P-1 packs can be seen below:

695

1100





2280

Accessories are packed on an order by order basis and the height of these packs is subject to change depending on the number and type of accessories required. However, the widths of these packs are generally restricted to the same widths of the P-1 panels (1080mm and 1280mm for 200P-1, and 1190mm for 110P-1).

©Copyright 👆 DINCEL



Loading Trucks


Dincel - Forms are required to be loaded and secured for the purpose of transportation to the nominated delivery address in accordance to the requirements and guidelines of the National Transport Commission, and the Roads and Traffic Authority.

Dincel Construction System licensed forklift operators assist in loading the truck. 200P-1 Packs are loaded onto the truck at a width of one ten pack and one twelve pack and 110P-1 packs are loaded with two twenty packs side by side, as described above. Additional dunnage (timber blocks/ packing) may be used to elevate the bottom packs to assist in loading and unloading. Generally, the packs are loaded at a three pack height; however a height of four packs can be achieved under certain circumstances. This will be explained in more detail later in this document.

The packs are generally secured to the truck via tie down straps placed over the timber frames (*not on the product itself*) and fastened accordingly by the trucking company. These straps can be used in conjunction with side gates or other bracing to further secure the load. It should be noted that ropes are an acceptable method of securing the packs to the truck, although they are not recommended due to their lower reliability.


All duties concerning load restraint are to be performed by the truck driver, and Dincel Construction System retains no responsibility for any damages that occur as a result of incorrect loading. The driver is required to sign for the load before it departs, stating that the load has been correctly loaded and secured. Refer to attached delivery docket required to be signed by the driver upon collecting the goods.

Generally, a single semi trailer can transport between eighteen (18) and twenty-four (24) packs at a time, depending on the lengths contained in the order. This is based on a truck pulling a forty-five foot trailer. It is the client's responsibility to ensure the truck sent is adequate to accept the load. This will be explained in more detail later in this document.




©Copyright PINCEL





Side view of loaded truck



©Copyright 🍯 DINCEL



Legal Requirements for Transportation by Trucks

All trucks must comply with the relevant laws as prescribed by the RTA. These laws include restrictions such as the maximum height and width of a load, along with strict load restraint guides. The following information was sourced from the National Transport Commission website (www.ntc.gov.au)

Dimensions for General Access Vehicles

Vehicles that have general access to the road system are limited to the following dimensions:

- A width of 2.5 metres
- A height of 4.3 metres (from the road)
- A length of 12.5 metres for a single vehicle and 19 metres for a combination (e.g. prime mover and semi-trailer or truck/trailer combination).
- A deck length of 13.7 metres for semi-trailers

Dimensions for Vehicles with Restricted Access (B-doubles and Road Trains)

These vehicles have the same height and width limits as general access vehicles and generally have the following maximum lengths:

- B-doubles 25 metres
- Double road train 36.5 metres
- Triple road train 53.5 metres

Load Restraint

All loads must be sufficiently restrained so as to eliminate load movement on a truck during transit. At no point is a vehicle permitted to move with an unrestrained load.

A load that is adequately restrained so it does not shift is required to withstand forces of at least:

- •80% of its weight in the forward direction
- •50% of its weight sideways and rearwards
- •20% of its weight vertically

Failure to comply with these requirements is illegal, and may result in heavy fines and prosecution.

Transporting Loads Four Packs High on Trucks

Upon receipt of special written request, Dincel Construction System can assist to load trucks up to four packs high. To conform with all relevant guidelines the following must be arranged to allow a four pack height:

- The deck height of the trailer must not exceed 1200mm to allow the truck to conform to the abovementioned height restrictions.
- Additional side bracing is required to prevent the load from shifting during transit. This side bracing must be of an equivalent height to the packs on the truck (3100mm), and



must be easily removed since the truck is loaded by forklift from both sides. This side bracing may come in the form of upright support brackets, high gates, or similar.

• In the case of taught liner and enclosed trailers, additional head room must be taken into account to allow straps to be thrown over the load and to ensure ease of loading by forklift.

Additional Considerations for Transportation by Trucks

In our experience, there are many factors that are often overlooked when customers arrange their own transport. Some of these factors are listed and explained below:

- The trucks ordered by the client are not always the same as the trucks that arrive on site. Regularly when picking up a load, a transport company will send whatever truck/s it has available at the time. This may or may not be exactly the same truck as you have asked for at the time of placing the order. It is between the client and the transport company to ensure that the trucks sent are of the correct length and style. If the wrong truck/trailer combination is sent, Dincel Construction System takes no responsibility for any material that does not fit on the truck as a result.
- The full deck of the trailer may not be available when the truck arrives on site. Trucks often carry additional items such as tarpaulins, gates, spare dunnage, and other equipment on the trailer to aid the driver. If such items are stored on the deck of the trailer this room cannot be used for loading your order. As a result the useable length of the trailer may be reduced for example, from 45 feet to as much as 41 feet.
- Some enclosed trailers contain fixed upright supports. These fixed upright supports will dictate what lengths can be loaded onto the trailer, and the position of the packs on the trailer.
- Some trailers feature adjustable mezzanine flooring, suspended by fixed upright supports. In this situation, the thickness of the mezzanine flooring must be added to the height of the trailer, and considerations must be given to the fixed upright supports in regard to the size and placement of the order on the truck.
- Not all trucks contain full length rails, allowing tie down straps to be placed at any position of the trailer. This may inhibit the positioning of packs on the trailer as the timber frames must be in alignment with the tie down straps to provide sufficient restraint.
- Twin deck trailers may limit the pack lengths that can be loaded onto the truck. For example, a trailer with a ten meter bottom deck and 3 meter top deck would not safely be able to transport a full load of six meter panels, due to the amount of overhang that would be present on the top deck.

©Copyright 🍯 DINCEL



Description of Packaging for Transport by Container

Container Dimensions

20th Concered Dumpered	20'x8'x8'6" ISO Type Dry Cargo Steel Container			
20ft General Purpose	Dimension		mm	ft
		Width	2438	8
		Height	2591	8
	Internal	Length	5900	19.4
		Width	2350	7.8
		Height	2393	7.1
	Inside cubic capacity		cu.m	cu.ft
			33.2	1172
	Opening		mm	ft
		Width	2338	7.8
		Height	2280	7.6

200P-1 PACKING

11 x 200P-1 panels are placed horizontally to pack the width of the container and 6 panels high (333.3 x 6 = 2m) with an amount of space available for accessories above the packed panels (see photos on page 10).

Transport capacity = 11 panels x 6 panels x length of panel (5.9m - 0.05) = 386 L/M or 128 m² per container (excluding accessories).

110-P1 PACKING

20 x 110P-1 panels are placed horizontally to pack the width of the container and 6 panels high (333.3 x = 2m) with an amount of space available for accessories above the packed panels.

Transport capacity = 20 panels x 6 panels x length of panel (5.9 - 0.05) = 702 L/M or 234 m² per container (excluding accessories).

PLEASE NOTE: the length of the container is reduced to 5.85m to allow for tolerances including damaged containers.

©Copyright **DINCEL**



Container Dimensions

	40'x8'x8'6'	40'x8'x8'6" ISO Type Dry Cargo Steel Container			
40ft General Purpose	Dimension		mm	ft	
	External	Length	12192	40	
		Width	2438	8	
	la la compañía	Height	2591	9	
	Internal	Length	12036	39.5	
		Width	2350	7.8	
		Height	2393	7.1	
	Inside cubic	capacity	cu.m	cu.ft	
			67.7	2390	
	Opening		mm	ft	
		Width	2338	7.8	
		Height	2280	7.6	

200P-1 PACKING

11 x 200P-1 panels are placed horizontally to pack the width of the container and 6 panels high (333.3 x 6 = 2m) with an amount of space available for accessories above the packed panels (see photos on page 10).

Transport capacity = 11 panels x 6 panels x length of panel $12m = 792 \text{ L/M or } 264 \text{ m}^2$ per container (excluding accessories).

110-P1 PACKING

20 x 110P-1 panels are placed horizontally to pack the width of the container and 6 panels high (333.3 x = 2m) with an amount of space available for accessories above the packed panels.

Transport capacity = 20 panels x 6 panels x length of panel $12m = 1440 \text{ L/M or } 480 \text{ m}^2$ per container (excluding accessories).

PLEASE NOTE: the length of the container is reduced to 12m to allow for tolerances including damaged containers.







PHOTO 1

PHOTO 2

Please contact Mr. Michael Hornby on (02) 9670 1633 or michaelh@dincel.com.au if you require further explanation.



COLLECTION DOCKET

PO Box 104 ST CLAIR NSW 2750 Ph: (02) 9670 1633 Fax: (02) 9670 6744 ABN: 78 083 839 614



SHIPMENT DATE:

DELIVERY NO: _____

SCHEDULE: _____

DOCUMENT: _____

SOLD TO:

DELIVER TO:

MODULE	LENGTH	QTY. ORDERED	QTY. SHIPPED	PACKS

I HAVE CHECKED THE PRODUCT LISTED IN THIS COLLECTION DOCKET AND CONFIRM THAT:

(i) I HAVE RECEIVED ALL PRODUCTS LISTED HEREIN.

(ii) THE PRODUCT RECEIVED AT PICK-UP ADDRESS IS IN GOOD ORDER.

(iii) THE PRODUCT HAS BEEN APPROPRIATELY LOADED AND RESTRAINED, AND IS SAFE FOR TRANSPORT.

NAME OF RECIPIENT

SIGNATURE

DATE

